

PLANNED TREE MAINTENANCE

Tree Works Notification		Created By:	
Public Scrutiny		Date:	
Tree Works reference number and schedule title			
Wards included within planned works:			
Abbey		East Chesterton	Queen Ediths
Arbury		Kings Hedges	Romsey
Castle		Market	Trumpington
Cherry Hinton		Newnham	West Chesterton
Coleridge		Petersfield	
Within following Council service areas:			
Highways		Housing	Parks
Size of schedule – based on number of trees included within:			
Small (< 10 trees)		Medium (11 - 50 trees)	Large (> 50 trees)
Brief description of the works			

Tree Works Notification

For tree works submitted under a 'Tree Works Notification' I refer you to Policy GM3 of the Cambridge City Council Citywide Tree Strategy 2016-2026 Part 2:

"All planned tree works will be published on the Council website and through site notices for the community to access at least 20 working days before implementation. The council sees this as an important tool for communicating to the local community about tree work planned for their area and the reasons why the works are necessary." <https://www.cambridge.gov.uk/tree-strategy>

The notification period will run for 20 days from the date of publication of the schedule.

The majority of the works contained within these schedules consists of minor pruning to address health and safety issues, or more significant works to remove trees that are obviously dead, dying or diseased, or replacement planting for trees that have been removed.

A brief outline of the planned works can be found in the table shown above however; full details of the planned works can be found within the attached schedules and maps.

Please note: where trees are due to be felled, these are marked on site with green tape.

Public Scrutiny

For tree works submitted for 'Public Scrutiny' A brief outline of the planned works which we wish to be publicly scrutinised can be found within the attached schedules and maps which will be available for ten working days following the date of publication.

The planned works could involve either removing healthy trees over 75mm in diameter as measured at 1.5m above ground level and/or any tree work or batch of works that will have a significant impact on the landscape character of an area as assessed by an arboricultural officer. This will include crown reductions of over 30% in branch length on trees that have not previously been reduced.

The table above provides details of the works which are open for public scrutiny, please note that some tree works schedules may contain other works in other service areas than those open to this level of scrutiny. The following details only relate to the significant works considered for scrutiny. Please note: where trees are

due to be felled, these are clearly marked on site with green tape.

I refer you to Policy GM5 of the Cambridge City Council [Citywide Tree Strategy 2016-2026 Part 2](#):

“When considering tree works on City Council land, the Council will invite resident and stakeholder comment regarding the following kinds of work:

- a) Any tree work which will have a significant impact on the character of an area.*
- b) Felling healthy trees of over 75mm diameter”*

If you wish to make a comment about any of the works proposed, please submit them via this link: [Comment on a tree work schedule](#). All unresolved objections to tree work subject to public scrutiny will be determined by the relevant Executive Councillor.

Location:

PMP Accordia

Site type:

Order no/ref:
Contract/Client Ref:
Item created: 02 February 2024

Priority of works:
Start on/after:
Complete by:

Tree/Item code	Species/Work required	Rate	Quantity	Cost
----------------	-----------------------	------	----------	------

Accordia (ACCGS), Trumpington

Sgl/1 (960015)	Elm (Unspecified) (Ulmus species) near multi stemmed acer (///places.list.cared)			
RGL	Rem - tree to ground level x2 dead elm stems. near multi stemmed acer.		1 tree	0.00
Sgl/13 (019860)	Maple (Field) (Acer campestre) (///rocky.economies.crust)			
CL4	Crown lift to 4m		1 tree	
Sgl/14 (019864)	Maple (Field) (Acer campestre) (///pines.nets.saying)			
CRB	C/R - to clear building by approx 3m		1 tree	0.00
Sgl/15 (019856)	Plane (London) (Platanus x hispanica) (///demand.model.deeply)			
CRB	C/R - to clear building by approx 5m		1 tree	0.00
Sgl/40 (019980)	Oak (English) (Quercus robur) (///report.milky.feared)			
CLR	C/L - over road to 5m		1 tree	0.00
Sgl/83 (020896)	Birch (Silver) (Betula pendula) (///data.guard.couple)			
RT1	Fell or dismantle the tree. Leave stump at 1m above ground level - leave trunk approx 3m high for habitat		1 tree	
Sgl/88 (020888)	Pine (Black) (Pinus nigra) (///with.robots.award)			
RFR	Rem - tree for replant		1 tree	0.00
Sgl/89 (020884)	Pine (Black) (Pinus nigra) (///cover.rift.really)			
RFR	Rem - tree for replant		1 tree	0.00
Sgl/108 (020844)	Pine (Corsican) (Pinus nigra var. maritima) (///librarian.muddy.chip)			
BRANC	Reduce specified branch by - Reduce codominant leader (facing SE) by 3-4m in height.		1 tree	
Sgl/127 (020384)	Plane (London) (Platanus x hispanica) (///love.penny.recall)			
RDW	Rem - deadwood - Top SW corner of tree is experiencing die back. I would appreciate some photos sent via whatsapp of the removed branches. - Jake		1 tree	0.00

Tree/Item code	Species/Work required	Rate	Quantity	Cost
Sgl/133 (021748)	Apple (Unspecified) (Malus species) (///extend.frogs.divisions)			
CL2.5	Crown lift to 2.5m		1 tree	
CRR	C/R - roadside by - prune back from road to prevent contact from traffic		1 tree	0.00
Sgl/142 (020340)	Lime (Common) (Tilia x europaea) (///juror.chose.falls)			
CRT	C/R - by - Reduce stem that faces Plane tree to just above the bat box.		1 tree	0.00
	- Reduce stem that faces houses by approx 4m.			
RPC	Rem - epicormics		1 tree	0.00
RDW	Rem - deadwood		1 tree	0.00
Sgl/147 (020336)	Plane (London) (Platanus x hispanica) (///part.daring.blues)			
RDW	Rem - deadwood - particularly piece approx 10m high over gravel footpath.		1 tree	0.00
Sgl/155 (020300)	Maple (Sycamore) (Acer pseudoplatanus) (///bound.souk.shrimp)			
RDW	Rem - deadwood - over road side		1 tree	0.00
Sgl/170 (020172)	Maple (Norway) (Acer platanoides) (///chain.branch.hills)			
RDW	Rem - deadwood		1 tree	0.00
Sgl/173 (381840)	Maple (Norway) (Acer platanoides) (///diary.kept.corner)			
RDW	Rem - deadwood		1 tree	0.00
Sgl/174 (381848)	Maple (Norway) (Acer platanoides) (///dozen.deep.miss)			
CLH	C/L - over highway to 3.5-4.5m car park		1 tree	0.00
CRL	C/R - to clear lamp by 0.5-1m (1m)		1 tree	0.00
RDW	Rem - deadwood		1 tree	0.00
Sgl/209 (021196)	Apple (Unspecified) (Malus species) (///cheek.clown.neon)			
RGL	Rem - tree to ground level - remove dead tree and stakes. leave mature epi that has grown from root stock		1 tree	0.00
Sgl/220 (020540)	Pine (Scot's) (Pinus sylvestris) (///reef.dawn.spices)			
CRL	C/R - to clear lamp by 0.5-1m		1 tree	0.00
Sgl/293 (019896)	Oak (English) (Quercus robur) (///images.tuck.jumpy)			
CRB	C/R - to clear building by - clear 3m between tree and building		1 tree	0.00
Sgl/439 (515540)	Amelanchier (Serviceberry) (Amelanchier laevis) (///pitch.played.moves)			
CL3	Crown lift to 3m		1 tree	



Expenditure code analysis :-

Expenditure code not specified

Schedule item analysis :-

CLH	C/L - over highway to 3.5-4.5m	1 tree @ 0.00
CLR	C/L - over road to	1 tree @ 0.00
CRB	C/R - to clear building by	3 trees @ 0.00
CRL	C/R - to clear lamp by 0.5-1m	2 trees @ 0.00
CRR	C/R - roadside by	1 tree @ 0.00
CRT	C/R - by	1 tree @ 0.00
RDW	Rem - deadwood	7 trees @ 0.00
RFR	Rem - tree for replant	2 trees @ 0.00
RGL	Rem - tree to ground level	2 trees @ 0.00
RPC	Rem - epicormics	1 tree @ 0.00

Contractor:

Total cost: 0.00

Issued by:

Jake Camilleri

ARBORICULTURAL WORKS ORDER

Item Ref: 02166

Accordia (ACCGS), Trumpington

