

Planned Tree Works Consultation

Tree Works Reference number and Schedule title:			
Works Order Item	LWO 2648 knightly Avenue		
Lead Arboricultural Officer	Jake Camilleri		
Consultation Period:	Start date	06/10/2026	End date 26/10/2026
Planned Works Period:	Start date	28/10/2026	End date 28/12/2026

Locations included within planned works:

Location:			
Abbey ☐	Arbury ☐	Castle ☐	Cherry Hinton ☐
Coleridge ☐	East Chesterton ☐	Kings Hedges ☐	Market ☐
Newnham ☐	Petersfield ☐	Queen Ediths ☒	Romsey ☐
Trumpington ☐	West Chesterton ☐	South Cambridgeshire ☐	

Council service areas included within planned works:

Service:			
Highways ☐	Housing ☐	Parks and Open Spaces (including recreation grounds and LNRs) ☒	Allotments ☐
Closed Churchyards ☐	Crematorium and cemetery ☐	Commercial Property and car parks ☐	Drainage ☐

Type of works included within this schedule:

Option:	
Minor works, minor pruning and routine works with limited visual impact	☒
Significant works, major pruning or works with noticeable impact	☐
Major works, felling or removal of trees	☐
Planting works, new or replacement planting	☐

Street tree duty:

Option:	
Includes proposed felling of street trees (Highways Act 1980 duty applies)	☐
Does not include street trees subject to statutory duty	☒

Size of schedule

Option:	
Small, fewer than 10 trees	☐
Medium, 11 to 50 trees	☒
Large, more than 50 trees	☐

Brief description of the works:

Primarily general maintenance tasks. Removal of small dead trees.

About this consultation

Cambridge City Council publishes tree works instructed by the Tree Team through a single consultation process. While many works are instructed by the Tree Team, others may be requested by different Council services or external agents, the client. In such cases, the Tree Team provides professional arboricultural advice and oversight to help ensure compliance with Council policy and best practice. The client will be identified in the brief description of the works, and any representations received will be forwarded to the relevant Instructing Officer for consideration and resolution.

All planned tree works covered by this process are published on the Council's [Planned Tree Works Webpage](#) for a minimum of 20 days. Ward councillors and relevant service leads are notified at the same time. This allows residents, councillors and stakeholders to understand what works are proposed, where they are proposed, and why. The attached schedule and maps provide the full details of the proposed works. The summary on the front page is provided for ease of reference only.

This consultation process supports the delivery of Cambridge City Council's [Urban Forest Strategy](#), 2026 to 2036, which sets out the Council's vision, principles, and policies for protecting, managing, and growing the city's urban forest. The Strategy promotes transparency, proportionate decision making, and community engagement.

How comments are considered

Comments and objections received during the consultation period will first be considered by the Lead Arboricultural Officer.

Urgent health and safety works

Urgent works required for immediate safety reasons are delegated to the Lead Arboricultural Officer and may proceed without further referral.

Other works

Where objections cannot be resolved by the Lead Arboricultural Officer or Instructing Officer, matters may be referred to the relevant Executive Councillor. Considerations will include:

- the amenity value of the tree or trees and the likely impact of the works on the area, and
- whether the proposal is justified, considering reasons for and against.

Street tree duty to consult

Where works include the felling of street trees, the Council must comply with statutory consultation duties within the Highways Act 1980, unless the works are urgently required for safety.

Permits to Work

Some works may be undertaken by third parties under a [Permit to Work](#). These ensure work affecting Council trees meets arboricultural standards, legislation, and policy.

How to comment

Comments must be submitted via the [Comment on our planned tree works page](#) webform within the consultation period.



Location: Proj Knightly Avenue

Site type:

Issued By: Jake Camilleri

Order no/ref: 0

Contract/Client ref:

Instruction created: 30 September 2026

Contractor: Unallocated

Priority of works:

Start on/after: 30 September 2026

Complete by:

Code	Species/Work required	Rate	Qty	Total
Knightly Avenue, Queen Ediths				
Sgl/20.00 (564488)	Carpinus betulus (Hornbeam (Common)) - tree in green space central to site. ///former.resist.ages			
CL2.5	Crown lift to 2.5m		1 tree(s)	£0.00
Sgl/19.00 (564492)	Carpinus betulus (Hornbeam (Common)) - tree in green space central to site. ///survey.able.closed			
CL4	Crown lift to 4m		1 tree(s)	£0.00
Sgl/23.00 (564496)	Carpinus betulus (Hornbeam (Common)) - tree in green space central to site. ///motion.sleepy.period			
CL2.5	Crown lift to 2.5m - - lift and prune away from path		1 tree(s)	£0.00
Sgl/29.00 (564504)	Tilia cordata (Lime (Small Leaved)) - tree in green space central to site. ///skinny.tent.season			
CL2.5	Crown lift to 2.5m - - ensure sign is cleared, prune into mainstem where necessary.		1 tree(s)	£0.00
RPC	Rem - epicormics		1 tree(s)	£0.00
Sgl/25.00 (564512)	Fagus sylvatica (Beech (Common)) - tree on green space central to site. ///nation.zooms.influencing			
RSK	REM - stake		1 tree(s)	£0.00
Sgl/18.00 (564524)	Betula pubescens (Birch (Downy)) - tree on Green space central to site ///pile.rescue.union			
RSK	REM - stake - - remove stakes		1 tree(s)	£0.00
YTM	Young tree maintenance - - remove dead top		1 tree(s)	£0.00
Sgl/14.00 (564548)	Malus species (Apple (Unspecified)) - see map ///energy.tools.mutual			
\$WR	Recommended Works - see Comments - Remove ties and stakes.remove 5 lowest limbs, prune away from path by 1m.		1 tree(s)	£0.00
Sgl/15.00 (564552)	Malus species (Apple (Unspecified)) - see map ///woes.spoil.effort			



Code	Species/Work required	Rate	Qty	Total
\$WR	Recommended Works - see Comments - - remove ties and stakes- remove 4 lowest limbs.		1 tree(s)	£0.00
Sgl/48.00 (982326)	Quercus robur (Oak (English)) - see map ///stiff.tested.wiped			
RBR	Rem - tree by root		1 tree(s)	£0.00
Sgl/49.00 (982327)	Acer campestre (Maple (Field)) - see map ///drill.gold.insect			
\$WR	Recommended Works - see Comments - - Remove stakes and ties		1 tree(s)	£0.00
Sgl/50.00 (982328)	Acer campestre (Maple (Field)) - see map ///watch.reader.swan			
\$WR	Recommended Works - see Comments - - Remove stakes and ties- lift lowest branches out of walkway		1 tree(s)	£0.00
Sgl/51.00 (982329)	Acer campestre (Maple (Field)) - see map ///offer.milky.even			
\$WR	Recommended Works - see Comments - - Remove stakes and ties		1 tree(s)	£0.00
Sgl/52.00 (982330)	Acer campestre (Maple (Field)) - see map ///crew.groups.elder			
\$WR	Recommended Works - see Comments - - Remove stakes and ties		1 tree(s)	£0.00
Sgl/53.00 (982331)	Acer campestre (Maple (Field)) - see map ///moving.meals.nails			
\$WR	Recommended Works - see Comments - - Remove stakes and ties		1 tree(s)	£0.00
Sgl/54.00 (982332)	Acer campestre (Maple (Field)) - see map ///grows.froze.heat			
\$WR	Recommended Works - see Comments - - Remove stakes and ties		1 tree(s)	£0.00
Sgl/55.00 (982333)	Acer campestre (Maple (Field)) - see map ///rivers.retire.claim			
\$WR	Recommended Works - see Comments - - Remove stakes and ties- lift subsiding branches		1 tree(s)	£0.00
Sgl/57.00 (982335)	Acer campestre (Maple (Field)) - see map ///elder.lights.model			
\$WR	Recommended Works - see Comments - - Remove stakes and ties- lift lowest limbs facing walkway, prune into mainstem and sidelimbs as necessary.		1 tree(s)	£0.00



Code	Species/Work required	Rate	Qty	Total
Sgl/58.00 (982336)	Tilia tomentosa (Lime (Silver)) - in row ///spicy.refers.oddly			
RSK	REM - stake - - remove stake and ties		1 tree(s)	£0.00
Sgl/59.00 (982337)	Tilia tomentosa (Lime (Silver)) - in row ///trap.boats.police			
RSK	REM - stake - - remove stake and ties		1 tree(s)	£0.00
Sgl/60.00 (982338)	Tilia tomentosa (Lime (Silver)) - in row ///atoms.sobs.riding			
RSK	REM - stake - - remove stake and ties		1 tree(s)	£0.00
Sgl/61.00 (982339)	**Unidentified** (Unidentified) - in grass area ///harp.period.album			
RBR	Rem - tree by root		1 tree(s)	£0.00
Sgl/62.00 (982340)	**Unidentified** (Unidentified) - in grass area ///window.reader.notice			
RBR	Rem - tree by root		1 tree(s)	£0.00
Sgl/63.00 (982341)	**Unidentified** (Unidentified) - in grass area ///apple.prone.tinsel			
RBR	Rem - tree by root		1 tree(s)	£0.00
Sgl/64.00 (982342)	**Unidentified** (Unidentified) - in grass area ///flame.nearly.bared			
RBR	Rem - tree by root		1 tree(s)	£0.00
Sgl/66.00 (982344)	Tilia tomentosa (Lime (Silver)) - in row ///agreed.neat.logs			
RSK	REM - stake - - remove stake and ties		1 tree(s)	£0.00
Sgl/67.00 (982345)	Tilia tomentosa (Lime (Silver)) - in row ///upon.rushed.noting			
RSK	REM - stake - - remove stake and ties		1 tree(s)	£0.00
Sgl/68.00 (982346)	Tilia tomentosa (Lime (Silver)) - in row ///locker.plots.grew			
RSK	REM - stake - - remove stake and ties		1 tree(s)	£0.00
Sgl/70.00 (982348)	**Unidentified** (Unidentified) - on grass area ///flesh.bucks.wisdom			
RBR	Rem - tree by root		1 tree(s)	£0.00
Sgl/75.00 (982353)	Acer campestre (Maple (Field)) - on edge - ///cloud.poem.cowboy			



Code	Species/Work required	Rate	Qty	Total
CLY	Crown lift by - - remove 3 lowest limbs over path, into mainstem if required.		1 tree(s)	£0.00
Sgl/77.00 (982355)	Betula pubescens (Birch (Downy)) - tree on Green space central to site ///lakes.olive.peanut			
CLT	C/L - to - 1m		1 tree(s)	£0.00
YTM	Young tree maintenance - - remove stakes. remove dead out of top.		1 tree(s)	£0.00
Sgl/80.00 (982358)	Sorbus aria 'Lutescens' (Sorbus (Whitebeam Cv.)) - on entrance to allotment parking ///cubes.react.duke			
RSK	REM - stake		1 tree(s)	£0.00
Sgl/81.00 (982359)	Sorbus aria 'Lutescens' (Sorbus (Whitebeam Cv.)) - next to pedestrian entrance ///tulip.crowned.images			
RSK	REM - stake		1 tree(s)	£0.00
Sgl/88.00 (982370)	Acer campestre (Maple (Field)) - beside car park in tree belt ///direct.potato.purely			
CRC	C/R - to clear - - use hedge trimmer to cut back vegetation encroaching on cars. up to a height of 4m		1 tree(s)	£0.00
Sgl/89.00 (982371)	Acer platanoides (Maple (Norway)) - beside car park in tree belt ///racing.hike.waddle			
CRC	C/R - to clear - - use hedge trimmer to cut back vegetation encroaching on cars. up to a height of 4m		1 tree(s)	£0.00
Sgl/90.00 (982372)	Acer platanoides (Maple (Norway)) - beside car park in tree belt ///pile.table.player			
CL4	Crown lift to 4m - - cutt back all vegetation over paths and car park.		1 tree(s)	£0.00
Sgl/92.00 (982374)	Acer platanoides (Maple (Norway)) - behind social hub in tree belt ///alive.spicy.twins			
CLT	C/L - to - - approx 6m. lifting over hub and compost bays.		1 tree(s)	£0.00



Knightly Avenue, Queen Ediths

